

Tabela objętości robót ziemnych

PIKIETAŻ	POWIERZCHNIA		OBJĘTOŚĆ		ZUŻYCIE		BILANS
	WYKOP	NASYP	WYKOP	NASYP	NA MIEJSCU	NADMIAR	
0.00	0.00	0.76					0.0
			0.00	6.79	0.0	-6.8	
7.00	0.00	1.18				-6.8	-6.8
			0.00	28.10	0.0	-28.1	
27.00	0.00	1.63				-34.9	-34.9
			0.50	74.00	0.5	-73.5	
77.00	0.02	1.33				-108.4	-108.4
			0.39	54.99	0.4	-54.6	
116.00	0.00	1.49				-163.0	-163.0
			0.00	44.15	0.0	-44.1	
143.00	0.00	1.78				-207.1	-207.1
			0.00	67.62	0.0	-67.6	
171.00	0.00	3.05				-274.8	-274.8
			0.00	52.73	0.0	-52.7	
190.00	0.00	2.50				-327.5	-327.5
			0.00	104.85	0.0	-104.8	
235.00	0.00	2.16				-432.3	-432.3
			0.00	81.22	0.0	-81.2	
272.00	0.00	2.23				-513.5	-513.5
			13.70	47.19	13.7	-33.5	
305.00	0.83	0.63				-547.0	-547.0
			7.08	14.16	7.1	-7.1	
317.00	0.35	1.73				-554.1	-554.1
			8.93	129.28	8.9	-120.4	
368.00	0.00	3.34				-674.5	-674.5
			0.00	114.69	0.0	-114.7	
397.00	0.00	4.57				-789.2	-789.2
			0.00	70.85	0.0	-70.8	
410.00	0.00	6.33				-860.0	-860.0
			0.00	263.87	0.0	-263.9	
459.00	0.00	4.44				-1123.9	-1123.9
			0.00	92.22	0.0	-92.2	
476.00	0.00	6.41				-1216.1	-1216.1
			0.12	48.48	0.1	-48.4	
488.00	0.02	1.67				-1264.5	-1264.5
			110.04	47.04	47.0	63.0	
544.00	3.91	0.01				63.0	-1201.5
			140.16	1.68	1.7	138.5	
592.00	1.93	0.06				201.5	-1063.0
			79.42	5.72	5.7	73.7	
636.00	1.68	0.20				275.2	-989.3
			71.17	6.45	6.5	64.7	
679.00	1.63	0.10				339.9	-924.6
			92.16	2.40	2.4	89.8	
727.00	2.21	0.00				429.7	-834.8
			106.95	0.23	0.2	106.7	
773.00	2.44	0.01				536.4	-728.1
			156.55	0.31	0.3	156.2	
835.00	2.61	0.00				692.6	-571.9
			22.05	0.14	0.1	21.9	
844.00	2.29	0.03				714.5	-549.9
RAZEM			809.20	1359.15	94.7		